



Total permitted animal capacity from all permits for this site:

80,000 chicken broilers

In consideration of Decision Summaries RA10017, RA10017A and RA10017B, Approval RA10017B is issued to:

Name: John & Jacquie Campmans (the "permit holder")
Address: RR3 Site 10 Box 1 Olds AB T4H 1P4
Contact person: John Campmans

Permitted construction (based on the submitted site plan):

- Broiler barn 1 (134 m x 22 m)
- Broiler barn 2 (134 m x 22 m)

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that act.

The permit holder shall adhere to the descriptions contained in the filed applications for approvals RA10017, RA10017A and RA10017B, together with the site plan, building plans, and other attached documents, unless otherwise noted in the following conditions.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspections referenced in conditions # 2b and 3b, below.

Construction Conditions

1. Miscellaneous

The permit holders shall immediately cease construction of the broiler barns and contact the NRCB if the water table is observed to be 1 m or less from the bottom of the broiler barns' manure storage liners.

2. Broiler barn #1

- a. The concrete used to construct the manure storage and collection system in broiler barn 1 must have a minimum 28-day strength of 25 MPa. The permit holder shall provide a copy of the concrete supplier's invoice or other proof to the NRCB to confirm the specifications of the concrete used in the construction. This document must be provided to the NRCB prior to the inspection referenced in condition 2b below or by a later date stated by the NRCB.
- b. The permit holder shall not place livestock or manure in broiler barn 1 until the NRCB has inspected the barn and stated in writing that the facilities have been constructed in accordance with this Approval.
- c. The permit holder shall complete construction of broiler barn 1 by November 30, 2019, unless otherwise agreed upon in writing by the NRCB.



3. Broiler barn 2
 - a. The concrete used to construct the manure storage and collection system in broiler barn 2 must have a minimum 28-day strength of 25 MPa. The permit holder shall provide a copy of the concrete supplier's invoice or other proof to the NRCB to confirm the specifications of the concrete used in the construction. This document must be provided to the NRCB prior to the inspection referenced in condition 3b below or by a later date stated by the NRCB.
 - b. The permit holder shall not place livestock or manure in broiler barn 2 until the NRCB has inspected the barn and stated in writing that the facilities have been constructed in accordance with this Approval.
 - c. The permit holders shall complete construction of broiler barn 2 by November 30, 2019, unless otherwise agreed upon in writing by the NRCB.

This Approval becomes effective immediately. The Approval conditions will remain in effect unless amended in writing by the NRCB.

Approval RA10017A is hereby cancelled and is no longer in effect, unless Approval RA10017B is held invalid, in which case Approval RA10017A will remain in effect.

April 10, 2019

(Original Signed)
Francisco Echegaray, P.Ag.
Approval Officer