
In consideration of Decision Summary RA18008A, Authorization RA18008A is issued to:

Name: Hutterian Brethren of Red Willow (the “permit holder”)
Address: Box 940 Stettler AB T0C 2L0
Contact person: Tim Hofer

Permitted construction (based on the submitted site plan):

- Earthen liquid manure storage (EMS) (91.4 m x 91.4 m x 5.5 m)

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that act.

The permit holder shall adhere to the descriptions contained in the filed application for RA18008 and RA18008A, together with the site plan, building plans, engineering reports and other attached documents, unless otherwise noted in the following conditions.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection referenced in condition #2 below.

The permit holder is responsible for all costs associated with monitoring, sampling, testing, recording and reporting requirements.

Construction conditions

1. The permit holder shall provide the NRCB with a written construction completion report for the earthen liquid manure storage. The report shall be stamped and signed by a “professional engineer,” as defined in the Standards and Administration Regulation, and shall:
 - Certify that the EMS was constructed at the location specified in the site plan provided with the application;
 - Certify that the liner material used in the EMS is the same material that was submitted for hydraulic conductivity testing;
 - Certify that the EMS was constructed according to the recommended construction procedures in the December 28, 2017 - Almor Testing Services Ltd. report;
 - Provide the vertical distance from the water table to the bottom of the EMS liner material at the time of construction;
 - Provide the constructed EMS dimensions, including elevations below and above grade, liner thickness, berm height, and side slopes.

The permit holder shall not place manure in the EMS until the report has been reviewed and accepted in writing by the NRCB.

2. The permit holder shall not allow manure into the new EMS until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.

3. The permit holder shall complete construction of the new EMS prior to November 30, 2020. Upon request, this deadline may be extended by the NRCB in writing.

This Authorization becomes effective immediately. Authorization RA18008A should be read in conjunction with previously issued Approvals RA11031 and RA11031A and Authorizations RA10021, RA12037 and RA13016, which remain in effect. The Authorization conditions will remain in effect unless amended in writing by the NRCB.

April 24, 2020

(Original Signed)
Francisco Echegaray, P.Ag.
Approval Officer