



Total permitted animal capacity from all permits for this site:

31,000 chicken layers (plus associated pullets)
1,500 ducks / 300 geese
2 dairy cows

In consideration of Decision Summary RA19049A, Approval RA19049A is issued to:

Name: Rosalind Hutterite Colony (the "permit holder")
Address: Box 1570 Camrose AB T4V 1X4
Contact person: Mike Stahl

Permitted construction (based on the submitted site plan):

- layer barn #2 (110 m x 25.6 m)
- manure collection shed #2 (30.5 m x 12.2 m)

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that act.

The permit holder shall adhere to the descriptions contained in the filed application for Approvals RA19049 and RA19049A, together with the site plan, building plans, engineering reports and other attached documents, unless otherwise noted in the following conditions.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection dates to schedule the inspection referenced in conditions #2 and 5.

The permit holder is responsible for all costs associated with monitoring, sampling, testing, recording and reporting requirements.

Construction conditions

Layer barn #2

1. The permit holder shall provide documentation to confirm that the manure storage and collection portions of the layer barn #2 has been constructed with a concrete thickness of 6", a strength of 32 Mpa at 56 days, using type 50 or equivalent cement, and having a size and separation of the concrete reinforcement (glass fiber reinforced polymer rebar) of 10 mil at 12" on center.
2. The permit holder shall not allow livestock or manure in the new layer barn #2, until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.
3. The permit holder shall complete construction of the manure collection and storage portions of the new layer barn #2 prior to December 31, 2021. Upon request, this deadline may be extended by the NRCB in writing.



Manure collection shed #2

4. The permit holder shall provide documentation to confirm that the manure storage and collection portions of the manure collection shed #2 has been constructed with a concrete thickness of 6", a strength of 32 Mpa at 56 days, using type 50 or equivalent cement, and having a size and separation of the concrete reinforcement (glass fiber reinforced polymer rebar) of 10 mil at 12" on center.
5. The permit holder shall not allow manure in the new manure collection shed #2, until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.
6. The permit holder shall complete construction of the manure collection and storage portions of the new manure collection shed #2 prior to December 31, 2021. Upon request, this deadline may be extended by the NRCB in writing.

This approval becomes effective immediately. The approval conditions will remain in effect unless amended in writing by the NRCB.

Approval RA19049 is hereby cancelled and is no longer in effect, unless Approval RA19049A is held invalid, in which case the previous permit will remain in effect.

May 14, 2020

(Original Signed)
Francisco Echegaray, P.Ag.
Approval Officer

Approval RA19049A – Appendix

Existing permitted facilities

- chicken barn #1 (63.4 m x 33.5 m) RA07003A
- duck and geese barn (21.3 m x 12.2 m) RA07003A
- covered concrete pad #1 (25.9 m x 8.5 m) RA100043

Already met construction conditions

(brought forward from Approval RA07003A)

1. A completion report confirming the chicken barn liner material and construction procedures, prepared by a qualified third party, must be provided to the NRCB prior to manure entering the chicken barns.
2. A completion report confirming the duck and goose barns liner material and construction procedures, prepared by a qualified third party, must be provided to the NRCB prior to manure entering the duck and goose barns.
3. Construction of the manure collection and storage portions of the chicken barns must be completed prior to December 31, 2010 unless otherwise agreed upon by the NRCB
4. Construction of the manure collection and storage portions of the duck and goose barn must be completed prior to December 31, 2010 unless otherwise agreed upon by the NRCB.
5. The manure storage portion of the chicken barns must be inspected by NRCB personnel prior to animals or manure being placed in the new barns.
6. The manure storage portion of the duck and goose barn must be inspected by NRCB personnel prior to animals or manure being placed in the new barn.

(brought forward from Authorization RA10043)

7. A copy of the concrete supplier's invoice or concrete test results must be provided to confirm the concrete specifications meet the technical guideline "TG 2004 – 02: Concrete Manure Liner Guideline" prior to manure being placed in the new covered concrete pad, unless otherwise agreed upon, in writing, by the NRCB.
8. Construction of the manure collection and storage portions of the CFO facility must be completed prior to November 30, 2013, unless otherwise agreed upon, in writing, by the NRCB.
9. The manure storage portion of the new solid manure concrete pad must be inspected by NRCB personnel prior to manure being placed in the new concrete pad.