
In consideration of Decision Summary RA20003, Authorization RA20003 is issued to:

Name: Adrianus and Antonia VandenBroek (the “permit co-holders”)
Address: RR1 Site 5 Box 30 Olds AB T4H 1P2
Contact person: Adrianus (Arie) VandenBroek

Permitted construction (based on the submitted site plan):

- Maternity barn 68.6 m x 53.3 m with manure pit (67 m x 4.6 m x 2.5 m)

Ancillary facilities:

- Drive through area 15.2 m x 53.3 m

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that act.

The permit holder shall adhere to the descriptions contained in the filed applications municipal development permit #DP152-99 and DP99-152, NRCB Approval RA11051 and Authorization RA20003 together with the site plan, building plans, and other attached documents, unless otherwise noted in the following conditions.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection in conditions #4.

The permit holder is responsible for all costs associated with monitoring, sampling, testing, recording and reporting requirements.

Construction conditions (maternity barn with manure pit)

1. The permit holder shall construct the concrete liner of the manure storage and collection system in the maternity barn category D (solid manure – dry) in Technical Guideline Agdex 096-93 “Non-Engineered Concrete Liners for Manure Collection and Storage Areas.” The permit holder shall provide documentation that the concrete used for the manure collection and storage areas meets the required specifications. This document must be provided to the NRCB prior to the inspection referenced in condition #4 below or by a later date stated by the NRCB.
2. The permit holder shall construct the concrete liner of the manure storage and collection system of the manure pit and scrape alleys of the maternity barn to meet the specifications for category B (liquid manure shallow pits) and category C (solid manure – wet) in Technical Guideline Agdex 096-93 “Non-Engineered Concrete Liners for Manure Collection and Storage Areas.” The permit holder shall provide documentation that the concrete used for the manure collection and storage areas meets the required specifications. This document must be provided to the NRCB prior to the inspection referenced in condition #4 below or by a later date stated by the NRCB.



3. The permit holder shall complete the construction of the maternity barn with manure pit prior to December 31, 2022. Upon written request, this deadline may be extended by the NRCB in writing.
4. The permit holder shall not place livestock or manure in the maternity barn with manure pit until the NRCB have inspected it and stated in writing that the maternity barn with manure pit has been constructed in accordance with the terms and conditions of this authorization.

This authorization becomes effective immediately, and is to be read in conjunction with previously issued Approval RA11051. The permit conditions will remain in effect unless amended in writing by the NRCB.

June 10, 2020

(Original signed)

Julie Wright
Approval Officer