

---

In consideration of Decision Summary RA20033, Authorization RA20033 is issued to:

Name: Scova Farms Inc. (the “permit holder”)  
Address: RR1 Site 1 Box 4 Ponoka AB T4J 1R1  
Contact person: Scott Ingwersen

**Permitted construction** (based on the submitted site plan):

- remove a dividing wall between the two existing liquid manure storages to create a single liquid manure storage (108.8 metres x 112.8 metres x 5.5 metres deep)

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that act.

The permit holder shall adhere to the descriptions contained in the filed application together with the site plan, building plans, engineering reports and other attached documents, unless otherwise noted in the following conditions.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection referenced in condition 2.

The permit holder is responsible for all costs associated with monitoring, sampling, testing, recording and reporting requirements.

**Construction conditions**

1. The permit holder shall provide the NRCB with a written construction completion report for the modified liquid manure storage. The report shall be stamped and signed by a “professional engineer,” as defined in the Standards and Administration Regulation, and shall:
  - Certify that the soil liner under the former dividing wall was constructed under the supervision of an engineer
  - Certify that the soil liner under the former dividing wall was constructed at the location specified in the site plan provided with the application.
  - Certify that the material used to construct the liner under the former dividing wall is the same material that was submitted for hydraulic conductivity testing.
  - Certify that the soil liner under the former dividing wall was constructed according to the recommended construction procedures in the June 4, 2020 Al-Terra Engineering report.
  - Provide details of the joint between the synthetic liner and the compacted liner

This report must be provided to the NRCB before the inspection referenced in condition #2, or by a later date stated by the NRCB.

2. The permit holder shall not allow manure in the modified portions of the liquid manure storage until, these modified portions of the facility have been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.
3. The permit holder shall complete construction of the soil liner under the former dividing wall prior to November 30, 2021. Upon request, this deadline may be extended by the NRCB in writing.

This Authorization becomes effective immediately and must be read in conjunction with previously issued Approval RA16073. The Authorization conditions will remain in effect unless amended in writing by the NRCB.

September 10, 2020

(Original Signed)  
Francisco Echegaray, P.Ag.  
Approval Officer