



Total permitted animal capacity from all permits for this site:

55,000 chicken broilers

In consideration of Decision Summary RA16011A, Approval RA16011A is issued to:

Name: Colin Thiessen (the "permit holder")
Address: RR 1 Ferintosh AB T0B 1M0
Contact person: Colin Thiessen

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that act.

The permit holder shall adhere to the descriptions contained in the filed applications for RA16011 and RA18065, together with the site plans, building plans, and other attached documents, unless otherwise noted.

This Approval becomes effective immediately. The Approval conditions will remain in effect unless amended in writing by the NRCB.

Approval RA16011 and Authorization RA18065 are therefore cancelled and are no longer in effect, unless Approval RA16011A is held invalid following a review and decision by the NRCB's board members or by a court, in which case the previous permits will remain in effect.

April 16, 2021

(Original Signed)
Francisco Echegaray, P. Ag.
Approval Officer

Approval RA16011A – Appendix

Existing Permitted Facilities:

Deemed Registration

- Two-story barn (40.3 m x 14.1 m)

Registration RA15051

- Poultry barn (78 m x 18 m)

Authorization RA18065 (relocated)

- Poultry barn (41.8 m x 14.6 m)

Construction Conditions carried forward from Registration RA15051

The permit holder shall provide the NRCB with a written completion report for the manure collection and storage areas of the new poultry broiler barn (78 m x 18.3 m). The report shall be prepared by a qualified third party, and shall verify:

- the dimensions of the new barn;
- the type, and 28 day compressive strength, of the concrete used in the manure collection and storage areas of the new poultry barn;
- the concrete thickness and concrete reinforcement size and spacing in the manure collection and storage portions of the barn.
- that the facility was built according to the submitted construction plans.

The permit holder shall not allow livestock or manure in the new poultry barn (78 m x 18.3 m) until the facility has been inspected by NRCB personnel and determined by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.

The permit holder shall complete construction of the manure collection and storage portions of the new poultry barn (78 m x 18.3 m) prior to January 31, 2018. Upon request, this deadline may be extended by the NRCB in writing.

Construction Conditions carried forward from Authorization RA18065

The concrete used to construct the liner of the relocated broiler barn (41.8 m x 14.6 m) must meet the specification for category D (solid manure – dry) in Technical Guideline Agdex 096-93 “Non-Engineered Concrete Liners for Manure Collection and Storage Areas.” The permit holder shall provide written confirmation, from a qualified third party, confirming that the concrete used for the manure collection and storage areas meets the required specification.



The permit holder shall not allow livestock or manure in the relocated broiler barn (41.8 m x 14.6 m) until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.

The permit holder shall complete construction of the manure collection and storage portions of the relocated broiler barn (41.8 m x 14.6 m) prior to November 30, 2019. Upon request, this deadline may be extended by the NRCB in writing.

Within one year, after relocating the broiler barn (41.8 m x 14.6 m), the permit holder shall decommission the existing concrete liner, of the relocated broiler barn, according to Technical Guideline Agdex 096-90, "Closure of Manure Storage Facilities and Manure Collection Areas."