



Total permitted animal capacity from all permits for this site:

130 milking cows (plus associated dries and replacements)
20,000 chicken breeders (plus associated pullets)
40,000 poultry broilers
4,000 poultry layers
180 swine farrow to finish
800 beef finishers
1,600 geese
500 turkey hens

In consideration of Decision Summary LA21008, Approval LA21008 is issued to:

Name: Hutterian Brethren of Wilson (the "permit holder")
Address: Box 99, Coaldale AB T1M 1M2
Contact person: Paul Wurz

Permitted construction (based on the submitted site plan):

- Poultry broiler breeder barn – 60 m x 25 m
- Poultry grower barn – 105 m x 31 m
- Relocate a solid manure storage pad – 22 m x 22 m

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that act.

The permit holder shall adhere to the descriptions contained in the filed application for Approval LA08001A, together with the site plan, building plans, engineering reports, and other attached documents, unless otherwise noted in the following conditions.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection in conditions #3 and #5.

The permit holder is responsible for all costs associated with monitoring, sampling, testing, recording and reporting requirements.

Construction conditions

Broiler Breeder and Grower Barn

1. The permit holder shall complete construction of the manure collection and storage portion of the Broiler Breeder and Pullet Barns prior to November 30, 2023. Upon request in writing, this deadline may be extended by the NRCB.
2. The concrete used to construct the manure storage and collection system in the Broiler Breeder and Grower Barns to have a minimum 28-day strength of 25 MPa and a maximum water to cement ratio of 0.55. The permit holder shall provide the NRCB with documentation that the concrete used for the manure collection and storage area meets the required



specifications. This document should be provided prior to the inspection cited in condition #3.

3. The permit holder shall not place manure or livestock in the Broiler Breeder and Grower Barns until the facilities have been inspected by the NRCB and determined (in writing) to have been constructed in accordance with the terms and conditions of this permit.

Solid Manure Storage Pad

4. The permit holder shall complete construction of the manure collection and storage portion of the Earthen Solid Manure Storage Pad prior to November 30, 2023. Upon request in writing, this deadline may be extended by the NRCB.
5. The permit holder shall not place manure on the Earthen Solid Manure Storage Pad until the facility has been inspected by the NRCB and determined (in writing) to have been constructed in accordance with the terms and conditions of this permit.

This approval becomes effective immediately. The approval conditions will remain in effect unless amended in writing by the NRCB.

Approval LA08001A is hereby cancelled and is no longer in effect, unless Approval LA21008 is held invalid, in which case the previous permit will remain in effect.

April 19, 2021

(original signed)
Joe Sonnenberg
Approval Officer



Approval LA21008 – Appendix

Existing Permitted Facilities

Authorization LA13004	<ul style="list-style-type: none"> • Dairy barn replacement - 60 m x 33.5 m • Earthen liquid manure storage - 80 m x 50 m x 3.9 m
Approval LA08001/ LA08001A	<ul style="list-style-type: none"> • Poultry broiler barn - 97.5 m x 21.3 m • Solid manure storage pad - 42 m x 42 m
Deemed	<ul style="list-style-type: none"> • Sow Barn - 50 m x 15 m • Grower and Finisher Barn - 60 m x 18 m • Broiler Barn - 98.5 m x 19.2 m • Layer Barn - 27.5 m x 7.5 m • Broiler, Turkey & Pullet Barn - 27.5 m x 7.7 m • Duck and Goose Barn - 17 m x 7 m • Dairy Barn - 70 m x 17 m • Dairy Pens - 80 m x 128 m • Beef Feedlot - 160 m x 120 m

Construction Conditions (brought forward from LA13004)

Completion Reports

- a) Written verification of the concrete strength, sulphate resistance, and joint sealing, by a qualified third party, must be provided to the NRCB prior to or at the time of inspection.

Inspections

- a) The manure storage portion of the replacement dairy barn and earthen liquid manure storage must be inspected by the NRCB personnel prior to animals or manure being placed in the replacement dairy barn and earthen liquid manure storage.

Construction Completion

- a) Construction of the manure collection and storage portions of the CFO facilities must be completed prior to May 01, 2016, unless otherwise agreed upon in writing by the NRCB.

Construction Conditions (brought forward from LA08001)

Completion Reports

- a) A completion report confirming the barn liner material and construction procedures, prepared by a qualified third party must be provided to the NRCB prior to animals entering the barn. A completion report confirming the earthen solid manure storage liner material and construction procedures, prepared by a professional engineer, must be provided to the NRCB prior to manure being placed on the storage.

Construction Completion

- a) Construction of the manure collection and storage portions of the CFO facilities must be completed prior to April 30, 2013 unless otherwise agreed upon by the NRCB.

Inspections

- a) The manure storage portion of the poultry broiler barns and the solid manure storage pad must be inspected by NRCB personnel prior to animals or manure being placed in the new barns and manure being placed on the new solid manure storage.