



---

In consideration of Decision Summary RA21034, Authorization RA21034 is issued to:

Name: Hutterian Brethren Church of Fairview (the “permit holder”)  
Address: RR1 Crossfield AB T0M 0S0  
Contact person: Peter Hofer

**Permitted construction** (based on the submitted site plan):

- duck and goose barn (24.3 x 15.2 m)
- solid manure storage pad (24.3 m x 18.3 m) attached to the barn

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that act.

The permit holder shall adhere to the descriptions contained in the filed application together with the site plan, building plans, and other attached documents, unless otherwise noted in the following conditions.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection in conditions #2 and 5.

**Construction conditions**

Duck and goose barn

1. The concrete used to construct the liner of the duck and goose barn must meet the specifications for category D (solid manure – dry), in Technical Guideline Agdex 096-93 “Non-Engineered Concrete Liners for Manure Collection and Storage Areas.” The permit holder shall provide written confirmation confirming that the concrete used for the manure collection and storage areas meets the required specification.
2. The permit holder shall not allow livestock or manure in the duck and goose barn, until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.
3. The permit holder shall complete construction of the manure collection and storage portions of the duck and goose barn prior to August 31, 2024. Upon request, this deadline may be extended by the NRCB in writing.

Concrete pad

4. The concrete used to construct the liner of the concrete pad must meet the specifications for category C (solid manure – wet), in Technical Guideline Agdex 096-93 “Non-Engineered Concrete Liners for Manure Collection and Storage Areas.” The permit holder shall provide written confirmation confirming that the concrete used for the manure collection and storage areas meets the required specification.



5. The permit holder shall not allow manure in the concrete pad, until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.
6. The permit holder shall complete construction of the manure collection and storage portions of the concrete pad barn prior to August 31, 2024. Upon request, this deadline may be extended by the NRCB in writing.

This Authorization becomes effective immediately and needs to be read in conjunction with previously issued Approval RA15016A. The Authorization conditions will remain in effect unless amended in writing by the NRCB.

August 10, 2021

(Original Signed)  
Francisco Echegaray, P.Ag.  
Approval Officer