



Total permitted animal capacity from all permits for this site:

140 milking cows (plus associated dries and replacements)

In consideration of Decision Summary BA21008, Registration BA21008 is issued to:

Name: Skycrest Holsteins Ltd. (the "permit holder")
Address: Box 85 Athabasca AB T9S 2A2
Contact person: Robert Crest

Permitted construction (based on the submitted site plan):

- new dairy barn – 90 m x 39 m
- earthen liquid manure storage – 49 m x 49 m x 5 m deep

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that act.

The permit holder shall adhere to the descriptions contained in the filed application together with the site plan, engineering report and other attached documents, unless otherwise noted in the following conditions.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection in conditions #3 and 5.

Construction conditions

Dairy barn

1. Construction completion deadline

The permit holder shall complete construction of the dairy barn prior to December 1, 2024. Upon request, this deadline may be extended by the NRCB in writing.

2. Concrete

The concrete used to construct the manure collection and storage liner of the dairy barn must meet the specifications for category B (liquid manure shallow pits) and category C (solid manure – wet [scrape alleys]) in Technical Guideline Agdex 096-93 "Non-Engineered Concrete Liners for Manure Collection and Storage Areas." The permit holder shall provide written proof to the NRCB confirming the specifications of the concrete used. This document must be provided to the NRCB prior to the inspection referenced in condition #3, below, or by a later date stated by the NRCB.

3. Post construction inspections (prior to populating facilities)

The permit holder shall not place livestock or manure in the dairy barn until the NRCB has inspected the facility and stated in writing that it has been constructed in accordance with this registration.



Earthen manure storage (EMS)

4. Construction completion deadline

The permit holder shall complete construction of the EMS prior to December 1, 2024. Upon request, this deadline may be extended by the NRCB in writing.

5. Post construction inspections (prior to populating facilities)

The permit holder shall not place manure in the EMS until the NRCB has inspected the facility and stated in writing that it has been constructed in accordance with this registration.

This registration becomes effective immediately. The registration conditions will remain in effect unless amended in writing by the NRCB.

Skycrest Holstein's deemed registration is hereby cancelled and is no longer in effect, unless Registration BA21008 is held invalid, in which case the deemed permit will remain in effect.

August 18, 2021

(Original signed)

Nathan Shirley
Approval Officer



Registration BA21008 – Appendix

Existing permitted facilities (from deemed permit)

- Calf barn – 37 m x 13 m
- Shelter – 9 m x 9 m
- 2 cattle shelters – 9 m x 18 m
- Dairy barn (to be repurposed into young stock barn) – 15 m x 50 m
- 4 cattle pens – 75 m x 120 m (total)