



Total permitted animal capacity from all permits for this site:

500 ewes and lambs
800 feeder lambs

In consideration of Decision Summary LA21020, Registration LA21020 is issued to:

Name: Hannah Logan and Dalin Van Hecke
Address: Box 68, Lomond AB, T0L1G0
Contact person: Hannah Logan

Permitted construction (based on the submitted site plan):

- Lambing barn 24.4 m x 79.3 m (80 ft. x 260 ft.)
- Eight pens for growing and replacing lambs 19.8 m x 19.8 m each (65 ft. x 65 ft. each)
- Catch basin 28 m x 15.5 m x 2.5 m deep

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that act.

The permit holder shall adhere to the descriptions contained in the filed application together with the site plan, building plans, engineering reports and other attached documents unless otherwise noted in the following conditions.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspections in conditions #3, #5, and #7.

The permit holder is responsible for all costs associated with testing, recording and reporting requirements.

Construction conditions

Lambing barn

1. The permit holder shall complete construction of the manure collection and storage portion of the lambing barn prior to November 30, 2024. Upon request in writing, this deadline may be extended by the NRCB.
2. The concrete used to construct the manure storage and collection system in the Lambing Barn to have a minimum 28-day strength of 25 MPa and a maximum water to cement ratio of 0.55. The permit holder shall provide the NRCB with documentation that the concrete used for the manure collection and storage area meets the required specifications. This document should be provided prior to the inspection cited in condition #3.
3. The permit holder shall not place manure or livestock in the Lambing Barn until the barn has been inspected by the NRCB and determined (in writing) to have been constructed in accordance with the terms and conditions of this permit.



Sheep Pens

4. The permit holder shall complete construction of the manure collection and storage portion of the sheep pens prior to November 30, 2024. Upon request in writing, this deadline may be extended by the NRCB.
5. The permit holder shall not place livestock or manure in the sheep pens until the pens have been inspected by the NRCB and determined (in writing) to have been constructed in accordance with the terms and conditions of this permit.

Catch basin

6. The permit holder shall complete construction of the manure collection and storage portion of catch basin prior to November 30, 2024. Upon request in writing, this deadline may be extended by the NRCB.
7. The permit holder shall not allow manure contaminated runoff to enter the catch basin until the facility has been inspected by the NRCB and determined (in writing) to have been constructed in accordance with the terms and conditions of this permit.

This registration becomes effective immediately. The registration conditions will remain in effect unless amended in writing by the NRCB.

October 15, 2021

(Original signed)

Joe Sonnenberg
Approval Officer