



Total permitted animal capacity from all permits for this site:

4,000 beef finishers

In consideration of Decision Summary LA22005, Approval LA22005 is issued to:

Name: Groenenboom Holdings Inc. (the “permit holder”)
Address: Box 65, Coalhurst AB T0L 0V0
Contact person: Erik Groenenboom

Permitted construction (based on the submitted site plan):

- Eight pens – 38 m x 61 m
- Three pens – 41 m x 61 m
- Two pens – 30 m x 61 m
- Catch basin – 59.73 m x 50.7 m x 3.94 m

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that act.

The permit holder shall adhere to the descriptions contained in the filed Application LA22005 together with the site plan, building plans, engineering reports and other attached documents, unless otherwise noted in the following conditions.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection in condition #4

Construction conditions

Construction report

1. The permit holder shall submit a final construction report, prepared by a qualified third party, confirming the location and dimension of the catch basin and the feedlot pens. This report must be submitted prior to the post construction inspection stated below.

Water Table

2. The permit holder shall immediately cease construction and immediately notify the NRCB if the water table is encountered within 1 m of the construction zone during construction.

Construction completion deadline

3. The permit holder shall complete construction of the manure collection and storage portions of the new feedlot pens with catch basin prior to December 31, 2023. Upon request, this deadline may be extended by the NRCB in writing.



Post construction inspection

4. The permit holder shall not place livestock or manure (manure contaminated runoff) in the new feedlot pens with catch basin until the NRCB has inspected the facilities and stated in writing that the facilities have been constructed in accordance with this approval.

Operating conditions

5. A fly control program is to be maintained during fly breeding season.
6. No spreading of manure is to occur within 30 m of the canal.

This approval becomes effective immediately. The approval conditions will remain in effect unless amended in writing by the NRCB.

Deemed municipal development permit 95-06 is hereby cancelled and is no longer in effect, unless Approval LA2205 is held invalid, in which case the previous permit will remain in effect.

May 12, 2022

(Original signed)

Carina Weisbach
Approval Officer



Approval LA22005 – Appendix

Existing permitted facilities

| Facility | Dimensions (m) | From |
|--------------|---|-----------------|
| Feedlot pens | 8 pens 30 m x 61 m each 2 pens 39 m x 61 m each 2 pens 52 m x 61 m each 2 pens 20 m x 43 m each 1 pen 20 m x 35 m | MD Permit 95-06 |

Construction conditions (brought forward from MD Permit 95-06)

1. The feedlot expansion is for 1,000 head effectively increasing the capacity of this feedlot to 2,000 head total.
2. All surface water is to be diverted around the feedlot.