



Total permitted animal capacity from all permits for this site:
10,000 chicken layers

In consideration of Decision Summary RA24026, Registration RA24026 is issued to:

Name: Courtney and Annabelle Unruh (the “co-permit holders”)
Address: RR 1 Dewberry, AB T0B 1G0
Contact person: Courtney Unruh

Permitted construction (based on the submitted site plan):

- Layer barn – 85.3 m x 18.3 m (280 ft. x 60 ft.) with attached manure storage pad – 15.2 m x 15.2 m (50 ft. x 50 ft.)

Ancillary structure:

- egg handling area – 15.2 m x 18.3 m (50 ft. x 60 ft.)

The co-permit holders shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that Act.

The co-permit holders shall adhere to the descriptions, the site plan, building plans, operating plan, and other attached documents included with filed Application RA24026.

The co-permit holders shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection in conditions 3 and 6.

Construction conditions

Layer barn

1. Construction completion deadline

The co-permit holders shall complete construction of the layer barn prior to December 1, 2026. Upon request, this deadline may be extended by the NRCB in writing.

2. Concrete

The concrete used to construct the manure collection and storage liner of the layer barn must meet the specifications for category D (solid manure – dry) in Technical Guideline Agdex 096-93 “Non-Engineered Concrete Liners for Manure Collection and Storage Areas”. The co-permit holders shall provide written proof to the NRCB confirming the specifications of the concrete used. This document must be provided to the NRCB prior to the inspection referenced in condition 3, below, or by a later date stated by the NRCB.

3. Post construction inspections (prior to populating facilities)

The co-permit holders shall not place livestock or manure in the layer barn until the NRCB has inspected the facility and stated in writing that it has been constructed in accordance with this registration.



Manure pad

4. Construction completion deadline

The co-permit holders shall complete construction of the manure pad prior to December 1, 2026. Upon request, this deadline may be extended by the NRCB in writing.

5. Concrete

The concrete used to construct the manure collection and storage liner of the manure pad must meet the specifications for category D (solid manure – dry) in Technical Guideline Agdex 096-93 “Non-Engineered Concrete Liners for Manure Collection and Storage Areas”. The co-permit holders shall provide written proof to the NRCB confirming the specifications of the concrete used. This document must be provided to the NRCB prior to the inspection referenced in condition 6, below, or by a later date stated by the NRCB.

6. Post construction inspections (prior to populating facilities)

The co-permit holders shall not place manure on the manure pad until the NRCB has inspected the facility and stated in writing that it has been constructed in accordance with this registration.

This registration becomes effective immediately. The registration conditions will remain in effect unless amended in writing by the NRCB.

March 6, 2025

(Original signed)

Nathan Shirley
Approval Officer