

In consideration of Decision Summary RA25012, Authorization RA25012 is issued to:

Name: Five Star Cattle Co. Ltd. (the "permit holder")

Address: Box 5238
Contact person: Pete Heidelberg

Permitted construction (based on the submitted site plan):

- Heifer shed (open-faced shelter) 126 m x 26 m
- Solid manure storage pad 15.2 m x 26 m

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that Act.

The permit holder shall adhere to the descriptions, the site plan, building plans, and other attached documents included with filed Application RA25012.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection in conditions 2 and 5.

The permit holder is responsible for all costs associated with recording, and reporting requirements (this includes post construction reports).

Construction conditions

Heifer shed

- 1. The concrete used to construct the liner of the new heifer shed must meet the specifications for category D (solid manure dry) in Technical Guideline Agdex 096-93 "Non-Engineered Concrete Liners for Manure Collection and Storage Areas.". The permit holder shall provide written confirmation, from a qualified third party, confirming that the concrete used for the manure collection and storage areas meets the required specifications.
- 2. The permit holder shall not allow livestock or manure in the new heifer shed, until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.
- The permit holder shall complete construction of the manure collection and storage portions
 of the new heifer shed prior to November 30, 2026. Upon request, this deadline may be
 extended by the NRCB in writing.

Solid manure storage pad

4. The concrete used to construct the liner of the solid manure storage pad must meet the specifications for category C (solid manure – wet) in Technical Guideline Agdex 096-93 "Non-Engineered Concrete Liners for Manure Collection and Storage Areas". The permit holder shall provide written confirmation, from a qualified third party, confirming that the



concrete used for the manure collection and storage areas meets the required specifications.

- 5. The permit holder shall not allow manure on the solid manure storage pad, until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.
- 6. The permit holder shall complete construction of the manure collection and storage portions of the solid manure storage pad prior to November 30, 2026. Upon request, this deadline may be extended by the NRCB in writing.

This authorization becomes effective immediately and needs to be read in conjunction with previously issued permit Approval RA22018. The authorization conditions will remain in effect unless amended in writing by the NRCB.

April 17, 2025

(Original signed) Lynn Stone Approval Officer