



Total permitted animal capacity from all permits for this site:

180,000 chicken broilers

In consideration of Decision Summary RA25031, Approval RA25031 is issued to:

Name: Battle River Broilers Ltd. (the "permit holder")
Address: PO Box 1705 Camrose, AB T4V 1X6
Contact person: Anthony Reimer

Permitted construction (based on the submitted site plan):

- Chicken broiler barns 1 - 4 – 121.9 m x 20.7 m each

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that Act.

The permit holder shall adhere to the descriptions, the site plan, building plans and other attached documents included with filed Application RA25031.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection in conditions 2, 5, 8 and 11.

The permit holder is responsible for all costs associated with monitoring, sampling, testing, recording, and reporting requirements (this includes post construction reports).

Construction conditions

Broiler barn 1

1. The concrete used to construct the liner of the manure collection and storage portions of broiler barn 1 to meet the specifications for category D (solid manure - dry) in Technical Guideline Agdex 096-93 "Non-Engineered Concrete Liners for Manure Collection and Storage Areas". The permit holder shall provide documentation to confirm the specifications of the concrete used to construct the manure storage and collection portions of broiler barn 1. This document must be provided to the NRCB prior to the inspection referenced in condition 2, below, or by a later date stated by the NRCB.
2. The permit holder shall not place livestock or manure in the new broiler barn 1 until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.
3. The permit holder shall complete construction of broiler barn 1 prior to July 31, 2027. Upon request, this deadline may be extended by the NRCB in writing.

Broiler barn 2

4. The concrete used to construct the liner of the manure collection and storage portions of broiler barn 2 to meet the specifications for category D (solid manure - dry) in Technical

Guideline Agdex 096-93 "Non-Engineered Concrete Liners for Manure Collection and Storage Areas". The permit holder shall provide documentation to confirm the specifications of the concrete used to construct the manure storage and collection portions of broiler barn 2. This document must be provided to the NRCB prior to the inspection referenced in condition 5, below, or by a later date stated by the NRCB.

5. The permit holder shall not place livestock or manure in the new broiler barn 2 until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.
6. The permit holder shall complete construction of broiler barn 2 prior to July 31, 2027. Upon request, this deadline may be extended by the NRCB in writing.

Broiler barn 3

7. The concrete used to construct the liner of the manure collection and storage portions of broiler barn 3 to meet the specifications for category D (solid manure - dry) in Technical Guideline Agdex 096-93 "Non-Engineered Concrete Liners for Manure Collection and Storage Areas". The permit holder shall provide documentation to confirm the specifications of the concrete used to construct the manure storage and collection portions of broiler barn 3. This document must be provided to the NRCB prior to the inspection referenced in condition 8, below, or by a later date stated by the NRCB.
8. The permit holder shall not place livestock or manure in the new broiler barn 3 until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.
9. The permit holder shall complete construction of broiler barn 3 prior to July 31, 2027. Upon request, this deadline may be extended by the NRCB in writing.

Broiler barn 4

10. The concrete used to construct the liner of the manure collection and storage portions of broiler barn 4 to meet the specifications for category D (solid manure - dry) in Technical Guideline Agdex 096-93 "Non-Engineered Concrete Liners for Manure Collection and Storage Areas". The permit holder shall provide documentation to confirm the specifications of the concrete used to construct the manure storage and collection portions of broiler barn 4. This document must be provided to the NRCB prior to the inspection referenced in condition 11, below, or by a later date stated by the NRCB.
11. The permit holder shall not place livestock or manure in the new broiler barn 4 until the facility has been inspected by NRCB personnel and confirmed by them, in writing, to have been constructed in accordance with the terms and conditions of this permit.
12. The permit holder shall complete construction of broiler barn 4 prior to July 31, 2027. Upon request, this deadline may be extended by the NRCB in writing.



This approval becomes effective immediately. The approval conditions will remain in effect unless amended in writing by the NRCB.

July 22, 2025

(Original signed)

Sarah Neff
Approval Officer