
In consideration of Decision Summary BA25014, Authorization BA25014 is issued to:

Name: De Wildt Dairy Ltd., and Cornelis and Maria de Wildt (the “co-permit holders”)
Address: RR1, Barrhead Alberta T7N 1N2
Contact person: Matthew de Wildt

Permitted construction (based on the submitted site plan):

- Pack barn – 91 m x 28 m
- Solid manure storage pad – 30 m x 30 m

The co-permit holders shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that Act.

The co-permit holders shall adhere to the descriptions, the site plan, building plans, operating plan, and other attached documents included with filed Application BA25014.

The co-permit holders shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection in condition 3 and 6.

Construction conditions

Pack barn

1. Construction completion deadline

The co-permit holders shall complete construction of the pack barn prior to December 1, 2028. Upon request, this deadline may be extended by the NRCB in writing.

2. Concrete

The concrete used to construct the manure collection and storage liner of the pack barn must meet the specifications for category D (solid manure – dry) in Technical Guideline Agdex 096-93 “Non-Engineered Concrete Liners for Manure Collection and Storage Areas.” The co-permit holders shall provide written proof to the NRCB confirming the specifications of the concrete used. This document must be provided to the NRCB prior to the inspection referenced in condition #3, below, or by a later date stated by the NRCB.

3. Post construction inspections (prior to populating facilities)

The co-permit holders shall not place livestock or manure in the pack barn until the NRCB has inspected the facility and stated in writing that it has been constructed in accordance with this authorization.

Solid manure storage pad

4. Construction completion deadline

The co-permits holder shall complete construction of the solid manure storage pad prior to December 1, 2028. Upon request, this deadline may be extended by the NRCB in writing.

5. Concrete

The concrete used to construct the manure collection and storage liner of the solid manure storage pad must meet the specifications for category C (solid manure - wet) in Technical



Guideline Agdex 096-93 "Non-Engineered Concrete Liners for Manure Collection and Storage Areas." The co-permit holders shall provide written proof to the NRCB confirming the specifications of the concrete used. This document must be provided to the NRCB prior to the inspection referenced in condition #6, below, or by a later date stated by the NRCB.

6. Post construction inspections (prior to populating facilities)

The co-permit holders shall not place livestock or manure in the solid manure storage pad until the NRCB has inspected the facility and stated in writing that it has been constructed in accordance with this authorization.

This authorization becomes effective immediately and needs to be read in conjunction with previously issued Registration BA05008B. The authorization conditions will remain in effect unless amended in writing by the NRCB.

August 11, 2025

(Original signed)

Nathan Shirley
Approval Officer