



**Total permitted animal capacity from all permits for this site:**

20,000 chicken layers  
55,000 chicken broilers  
12,000 chicken pullets  
400 geese  
1,000 ducks

---

In consideration of Decision Summary LA25036, Approval LA25036 is issued to:

Name: MacMillan Hutterian Brethren (the "permit holder")  
Address: RR 1, Cayley AB T0L 0P0  
Contact person: Elias Waldner

**Permitted construction** (based on the submitted site plan):

- two broiler barns (broiler barn 1 and 2) (121.9 m x 18.3 m each)
- pullet barn (63 m x 13.5 m) with attached, covered manure storage (19 m x 10 m)
- layer barn (118 m x 26 m) with attached, covered manure storage (15 m x 10 m)

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that Act.

The permit holder shall adhere to the descriptions, the site plan, building plans, engineering reports and other attached documents included with filed Application LA25036.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection in conditions #4, 8, 12, and 16.

The permit holder is responsible for all costs associated with reporting requirements (this includes post construction reports).

**Construction conditions**

**Broiler barn 1**

1. Water table

The permit holder shall immediately cease construction of broiler barn 1 and contact the NRCB if the water table is observed to be one meter or less from the bottom of the liner of the manure collection and storage areas.

2. Concrete

The concrete used to construct the manure collection and storage areas of broiler barn 1 must meet the specification for category D (solid manure – dry) in Technical Guideline Agdex 096-93 "Non-Engineered concrete liner for manure collection and storage areas". The permit holder shall provide a copy of the concrete supplier's invoice or proof from a third party to the NRCB to confirm the specifications of the concrete used in the construction. This document must be provided to the NRCB prior to the post construction inspection referenced in condition #4 below or by a later date stated by the NRCB.

3. Construction completion deadline  
The permit holder shall complete construction of the manure collection and storage portions of broiler barn 1 prior to December 30, 2030. Upon request, this deadline may be extended by the NRCB in writing.
4. Post construction inspection  
The permit holder shall not place livestock or manure in the manure storage or collection portions of broiler barn 1 until the NRCB has inspected the facility and stated in writing that the facility has been constructed in accordance with this approval.

### **Broiler barn 2**

5. Water table  
The permit holder shall immediately cease construction of broiler barn 2 and contact the NRCB if the water table is observed to be one meter or less from the bottom of the liner of the manure collection and storage areas.
6. Concrete  
The concrete use to construct the manure collection and storage areas of broiler barn 2 must meet the specification for category D (solid manure – dry) in Technical Guideline Agdex 096-93 “Non-Engineered concrete liner for manure collection and storage areas”. The permit holder shall provide a copy of the concrete supplier’s invoice or proof from a third party to the NRCB to confirm the specifications of the concrete used in the construction. This document must be provided to the NRCB prior to the post construction inspection referenced in condition #8 below or by a later date stated by the NRCB.
7. Construction completion deadline  
The permit holder shall complete construction of the manure collection and storage portions of broiler barn 2 prior to December 30, 2030. Upon request, this deadline may be extended by the NRCB in writing.
8. Post construction inspection  
The permit holder shall not place livestock or manure in the manure storage or collection portions of broiler barn 2 until the NRCB has inspected the facility and stated in writing that the facility has been constructed in accordance with this approval.

### **Pullet barn with attached manure storage**

9. Water table  
The permit holder shall immediately cease construction of the pullet barn with attached manure storage and contact the NRCB if the water table is observed to be one meter or less from the bottom of the liner of the manure collection and storage areas.
10. Concrete  
The concrete use to construct the manure collection and storage areas of the pullet barn with attached manure storage must meet the specification for category D (solid manure – dry) in Technical Guideline Agdex 096-93 “Non-Engineered concrete liner for manure

collection and storage areas". The permit holder shall provide a copy of the concrete supplier's invoice or proof from a third party to the NRCB to confirm the specifications of the concrete used in the construction. This document must be provided to the NRCB prior to the post construction inspection referenced in condition #12 below or by a later date stated by the NRCB.

**11. Construction completion deadline**

The permit holder shall complete construction of the manure collection and storage portions of the new pullet barn with attached manure storage prior to December 30, 2030. Upon request, this deadline may be extended by the NRCB in writing.

**12. Post construction inspection**

The permit holder shall not place livestock or manure in the manure storage or collection portions of the pullet barn with attached manure storage until the NRCB has inspected the facility and stated in writing that the facility has been constructed in accordance with this approval.

**Layer barn with attached manure storage**

**13. Water table**

The permit holder shall immediately cease construction of the chicken layer barn with attached manure storage and contact the NRCB if the water table is observed to be one meter or less from the bottom of the liner of the manure collection and storage areas.

**14. Concrete**

The concrete use to construct the manure collection and storage areas of the layer barn with attached manure storage must meet the specification for category D (solid manure – dry) in Technical Guideline Agdex 096-93 "Non-Engineered concrete liner for manure collection and storage areas". The permit holder shall provide a copy of the concrete supplier's invoice or proof from a third party to the NRCB to confirm the specifications of the concrete used in the construction. This document must be provided to the NRCB prior to the post construction inspection referenced in condition #16 below or by a later date stated by the NRCB.

**15. Construction completion deadline**

The permit holder shall complete construction of the manure collection and storage portions of the new layer barn with attached manure storage prior to December 30, 2030. Upon request, this deadline may be extended by the NRCB in writing.

**16. Post construction inspection**

The permit holder shall not place livestock or manure in the manure storage or collection portions of the layer barn with attached manure storage until the NRCB has inspected the facility and stated in writing that the facility has been constructed in accordance with this approval.



This approval becomes effective immediately. The approval conditions will remain in effect unless amended in writing by the NRCB.

August 21, 2025

(Original signed)

Carina Weisbach  
Approval Officer