

In consideration of Decision Summary LA25054, Authorization LA25054 is issued to:

Name: Hutterian Brethren Church of Jumbo Valley (the "permit holder")
Address: Box 730, Fort Macleod AB T0L 0Z0
Contact person: Marcus Tschetter

Permitted construction (based on the submitted site plan):

- Catch basin – 43 m x 31 m x 2.4 m deep

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that Act.

The permit holder shall adhere to the descriptions, the site plan, building plans, engineering reports and other attached documents included with filed Application LA25054.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection in condition #3.

The permit holder is responsible for all costs associated with monitoring, sampling, testing, recording, and reporting requirements (this includes post construction reports).

Construction conditions

Catch Basin

1. Construction completion report

The permit holder shall provide the NRCB with a written construction completion report for the catch basin. The report shall be stamped and signed by a "professional engineer," as defined in the Standards and Administration Regulation, and shall:

- Certify that the catch basin was constructed at the location specified in the site plan provided with the application;
- Confirm the size of the catch basin, including the depth below grade;
- Certify that the liner material used in the catch basin is the same material that was submitted for hydraulic conductivity testing;
- Provide the in-situ density test results of the constructed catch basin liner.

The permit holder shall not allow manure contaminated runoff to enter the catch basin until the report has been reviewed and accepted, in writing, by the NRCB.

2. Construction completion deadline

The permit holder shall complete construction of the catch basin prior to December 31, 2026. Upon request, this deadline may be extended by the NRCB in writing.



3. Post construction inspection

The permit holder shall not allow manure contaminated runoff to enter the catch basin until NRCB personnel have inspected the facility and confirmed, in writing, that it has been constructed in accordance with the terms and conditions of this permit.

Decommissioning of existing catch basin

4. The permit holder shall decommission the catch basin according to Agdex 096-90 for catch basin facilities posing a low risk to groundwater and surface water within one year of finishing the construction of the new catch basin.

This authorization becomes effective immediately and needs to be read in conjunction with previously issued permit Approval LA25019. The authorization conditions will remain in effect unless amended in writing by the NRCB.

August 29, 2025

(Original signed)

Carina Weisbach
Approval Officer