



# Application for Amendment

Application under the *Agricultural Operation Practices Act* to amend a permit for a confined feeding operation, manure collection area and/or manure storage facility(ies). ("Permit" means an NRCB-issued or grandfathered approval, registration, or authorization, including a grandfathered municipal development permit.)

## NRCB USE ONLY

☒ Approval ☐ Registration ☐ Authorization

**AMENDMENT**

NRCB Application number

**LA23048A**

Date Stamp

**NRCB APPLICATION**

**04 SEP 2025**

**RECEIVED**

## CONTACT INFORMATION

### Applicant Information

Name:

**Johan Bennen**

Corporate Name (if applicable)

**Hejo Farms**

Address:

(Street/P.O. Box)

City/Town:

**Coaldale**

Province:

**AB**

Postal Code:

**T1M 1M5**

### Agent consent (if applicable)

I, \_\_\_\_\_, hereby give consent for \_\_\_\_\_  
(name of applicant) (name of agent and company)

to act on my behalf or as my agent for this application.

Signed this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_

Signature of Applicant

## LOCATION OF DEVELOPMENT

Which permit do you wish to  
amend? (List permit number and  
issuing agency.)

**LA 23048**

Legal Land Description(s)

**SW-25-8-20 W4**

(Qtr-Sec-Twp-Rg-W Mer)

## APPLICATION DISCLOSURE

This information is collected under the authority of the *Agricultural Operation Practices Act (AOPA)*, and is subject to the provisions of the *Freedom of Information and Protection of Privacy Act*. This information is public unless the NRCB grants a written request that certain sections remain private.

Any construction prior to obtaining an NRCB permit is an offence and is subject to enforcement action, including prosecution.

I, the applicant, or applicant's agent, have read and understand the statements herein and acknowledge that the information provided in this application is true to the best of my knowledge.

Date of signing

**4-9-2025**

Corporate name (if applicable)

Print name

# Application for Amendment – contd.

## AMENDMENT INFORMATION REQUIREMENTS

### Instructions:

For each part of your permit that you would like amended, please detail what change you would like made and why, and how your proposed change will meet the AOPA requirements. You may attach additional pages to this form to provide this information.

Please note that an approval officer may require a page (or pages) of the Part 2 application forms to be completed as part of this application for amendment, depending on what changes are proposed.

The as built dimensions of the barns  
change concrete liner to natural clay liner

Approval LA23048 approved the construction of a new sheep facility with a concrete liner. This application for amendment seeks to amend the liner to a naturally occurring protective layer with the following as-built dimensions:

- Ewe/lambing barn: 36 m x 311.7 m (118' x 1022' 8")
- Feeder barn: 32.2 m x 120.9 m (105' 8" x 396' 8")

## Part 2 — Technical Requirements

Application under the *Agricultural Operation Practices Act* for a confined feeding operation, manure collection area and/or manure storage facility(ies)

### SOLID MANURE, COMPOST, & COMPOSTING MATERIALS: Barns, feedlots, & storage facilities - Naturally occurring protective layer

(complete a copy of this section for **EACH** barn, feedlot, and storage facility for solid manure, composting materials, or compost with a naturally occurring protective layer for the liner)

Facility description / name (as indicated on site plan)

1. Laminy Barn
2. feeder Barn

#### Manure storage capacity

	Length (m)	Width (m)	Depth below ground level (m)	<b>NRCB USE ONLY</b> Estimated storage capacity (m <sup>3</sup> )
1.	<u>1,022' 8"</u> <u>550 Feet</u>	<u>118 Feet</u>	<u>0</u>	
2.	<u>396 Feet</u>	<u>105 Feet</u>	<u>0</u>	
TOTAL CAPACITY				

☒ I plan to use a short-term solid manure storage (STMS) as part of my manure storage and handling plan for this CFO. (The AOPA requirements for STMS are set out in the NRCB [Short-Term Solid Manure Storage Requirements Fact Sheet](#).)

#### Surface water control systems

Describe the run-on and runoff control system

Under Roof


#### Naturally occurring protective layer details

Thickness of naturally occurring protective layer	_____ (m)	Provide details (as required) <u>see at the Report.</u>	
Soil texture	_____ % sand	_____ % silt	_____ % clay
Hydraulic conductivity - naturally occurring protective layer	Depth and type of soil tested	Hydraulic conductivity (cm/s)	Describe test standard used

Additional information (attach copies of soil test reports)

#### NRCB USE ONLY

Requirements met: ☐ YES ☐ NO  
 Condition required: ☐ YES ☐ NO  
 Report attached: ☐ YES ☐ NO



NOTE: 3D VIEWS SHOW LIMITED AMOUNT OF INFORMATION  
AND ARE PROVIDED TO ILLUSTRATE OVERALL CONTEXT  
ONLY.  
REFER TO DRAWINGS AND SPECIFICATIONS FOR DETAILED  
INFORMATION.

Structural Sheet List		
Sheet Number	Sheet Name	Rev
S001	Structural Cover Page	1
S101	Foundation Plan - NW and NE	0
S102	Foundation Plan - South, and Details	1
S103	Foundation Sections	1
S201	Mezzanine Floor Framing Plan and Sections	1
S211	Roof Framing Plan - NW and NE	0
S212	Roof Framing Plan - South	0
S301	Framing Elevations and Connection Details	0
S311	Roof Framing Sections	0
S312	Roof Framing Sections	1
S601	Structural Notes	0

Total Sheet Count: 11

#### 01 45 17 SITE REVIEWS

1. SITE REVIEWS OF EXCAVATION, SHORING & UNDERPINNING, GROUNDWATER INVESTIGATION & CONTROL, STRUCTURAL CAPACITY OF SOILS AND ROCKS, MATERIALS, & COMPACTION ARE TO BE PERFORMED BY THE GEOTECHNICAL CONSULTANT AS PER THEIR REQUIREMENTS.
2. THE CONTRACTOR MUST CONTACT GRUBS ENGINEERING TO PERFORM SITE REVIEWS AT THE FOLLOWING STAGES OF CONSTRUCTION:
  - FORMS AND REINFORCING FOR FOOTINGS AND/OR PILE CAPS
  - FORMS AND REINFORCING FOR FOUNDATION WALLS, CONCRETE PIERS, GRADE BEAMS AND/OR PLASTER
  - FORMS AND REINFORCING FOR STRUCTURAL SLABS AND TOPPING
  - REINFORCING AND CONCRETE FILL OF CONCRETE MASONRY WALLS, INCLUDING GRADE LEVELS, COLUMNS AND PLASTER, PRIOR TO PLACEMENT OF CONCRETE
3. OVERALL STRUCTURAL FRAMING, PRIOR TO APPLYING ARCHITECTURAL FINISHES. MORE THAN ONE (1) REVIEW MAY BE REQUIRED DEPENDING ON THE PHASES OF THE CONSTRUCTION.
4. CONSULTANT IS TO BE INFORMED SUFFICIENTLY PRIOR TO EACH REVIEW AS NOTED BELOW. THESE SITE REVIEWS BY CONSULTANTS ARE REQUIRED REGARDLESS OF INSPECTIONS & REVIEWS PERFORMED BY OTHER PARTIES ISSUING AGENCY FAILURE TO OBTAIN THESE SITE REVIEWS WILL RESULT IN THE CONSULTANT NOT ISSUING THE LETTERS OF ASSURANCE WHICH MAY BE REQUIRED WHEN APPLYING FOR OCCUPANCY PERMIT.
5. TO ARRANGE A SITE REVIEW, PLEASE EMAIL: [info@grubsengineering.ca](mailto:info@grubsengineering.ca), INCLUDING CONTACT INFORMATION, PROJECT NAME AND LOCATION, TIMELINE, AND TYPE OF REVIEW REQUIRED (FOOTING, FRAMING, ETC.).
6. PLEASE PROVIDE MINIMUM OF 3 FULL BUSINESS DAYS' NOTICE FOR SITE REVIEWS.

#### 01 45 19 QUALITY ASSURANCE

1. COMPACTION TESTS ARE TO BE PERFORMED ON THE SLAB SUB-GRADE, THE SLAB BASE GRADES, AND FOR GRADES SENSITIVE FOOTINGS, AS REQUIRED, TO THE SATISFACTION OF THE GEOTECHNICAL CONSULTANT.
2. CONCRETE TESTS ARE TO BE PERFORMED DURING POURING OF ALL STRUCTURAL CONCRETE (INCLUDING BUT NOT LIMITED TO: FOOTINGS, FOUNDATION WALLS, PILE CAPS, GRADE BEAMS, PLASTER, RETAINING WALLS, SLAB ON GRADE, WALLS, COLUMNS, BEAMS, STRUCTURAL SLABS, MASONRY WALL CORSELS & MORTAR AND D-DECK TOPPING) WITH COPIES OF THE TEST RESULTS SUBMITTED TO GRUBS ENGINEERING CORP. CONTRACTOR SHALL SUBMIT TO GRUBS ENGINEERING CORP. CERTIFICATES FOR QUALIFICATION OF WELDED STEEL FABRICATORS AND ERECTORS.

#### 01 45 19 SHOP DRAWINGS

1. DISTRIBUTION OF SHOP DRAWINGS TO TRADES AFFECTED IS THE RESPONSIBILITY OF THE CONTRACTOR.
2. CONSULTANT'S REVIEW OF SHOP DRAWINGS AND DATA SHEETS COVERS GENERAL DESIGN CONCEPT ONLY. ERRORS OR DISCREPANCIES WILL BE NOTICED IF NOTICED, BUT THIS REVIEW WILL NOT RELIEVE THE CONTRACTOR FROM HIS RESPONSIBILITY TO COMPLETE THE WORK AS SHOWN AND SPECIFIED IN THE CONTRACT DOCUMENTS.
3. SHOP DRAWING SUBMITTALS AS REQUIRED FOR EACH TRADE SHALL CONSIST OF ONE (1) ELECTRONIC FILE FOR EACH REQUIRED SHOP DRAWING, MUST HAVE EVIDENCE OF REVIEW BY GENERAL CONTRACTOR AND BE SUBMITTED A MINIMUM OF TEN (10) WORKING DAYS PRIOR TO DATE REVIEWED SUBMITTALS WILL BE NEEDED.



**EAGLE BUILDERS**



**grubs**



**PROFESSIONAL ENGINEER**



**PROFESSIONAL ENGINEER**



**PROFESSIONAL ENGINEER**



**PROFESSIONAL ENGINEER**



**PROFESSIONAL ENGINEER**




**PROFESSIONAL ENGINEER**





**PROFESSIONAL ENGINEER**













- 01 33 16 DESIGN LOADS**
1. THE APPLICABLE PROVINCIAL OR NATIONAL BUILDING CODE USED FOR THIS PROJECT IS: NATIONAL BUILDING CODE ALBERTA 2023 EDITION
  2. ALL STRUCTURAL ELEMENTS ARE DESIGNED TO CONFORM TO THE SPECIFIED APPLICABLE PROVINCIAL OR NATIONAL BUILDING CODE
  3. REFERENCE LOADS USED IN THE STRUCTURAL DESIGN ARE:  
 GROUND SNOW LOAD:  
 $S_g = 2.5 \text{ psf (0.1 kPa)}$   
 LATERAL LOADS:  
 $W = 1.1 \text{ psf (0.05 kPa)}$   
 WIND SPEED: 110 mph (173 km/h)  
 WIND EXPOSURE: CATEGORY II  
 ROOFS: 2020a (1.3 kN)  
 FLOORS: 2020b (0.9 kN)
  4. BUILDING DESIGN LOADS USED ARE:  
 a. ROOF:  
 DESIGN SNOW LOAD: 20.2 psf (1.0 kPa)  
 DESIGN DEAD LOAD (SELF-WEIGHT & SUPERIMPOSED): 12.0 psf (0.6 kPa)  
 NET FACTORED WIND UPLIFT: 14.0 psf (0.7 kPa)  
 b. ADDITIONAL LOADS DUE TO SNOW BUILD-UP ARE AS SHOWN ON THE ROOF FRAMING PLAN  
 c. SNOW LOAD SHOWN IS FOR ULTIMATE LIMIT STATE (ULS), FOR SERVICEABILITY LIMIT STATE (SLS) MULTIPLY BY 0.9  
 d. ADDITIONAL LOADS DUE TO MECHANICAL EQUIPMENT SHALL BE INCLUDED. REFER TO MECHANICAL DRAWINGS FOR LOCATIONS AND WEIGHTS  
 e. SECOND FLOOR:  
 DESIGN LIVE LOAD: 100.0 psf (4.8 kPa)  
 DESIGN DEAD LOAD (SELF-WEIGHT): 9.0 psf (0.4 kPa)  
 DESIGN DEAD LOAD (SUPERIMPOSED): 0.0 psf (0.0 kPa)

TYPE	DESIGN NAME	STEEL TYPE (FABRICATED U.S.)
B1	W8X24	50 ksi
B2	W10X15	50 ksi
B3	W12X24	11 ksi

TYPE	DESIGN NAME	STEEL TYPE (FABRICATED U.S.)
C1	W8X24	50 ksi
C2	W10X15	50 ksi
C3	W12X24	11 ksi

**A Roof Framing Plan - North West**  
1/16" = 1'-0"

**B Roof Framing Key Plan**  
1/4" = 1'-0"

**B Roof Framing Plan - North East**  
1/16" = 1'-0"

**EAGLE BUILDERS**

**grub4**

**PERMIT TO PRACTICE**


**PROFESSIONAL ENGINEER**

**Help Farms, Sheep Barn**  
Lethbridge County, Alberta

Roof Framing Plan - NEI  
and NEI

2019

0211



Roof Framing Key Plan  
1" = 160'-0"

Roof Framing Plan - South  
1/8" = 1'-0"

STEEL BEAM SCHEDULE		
Type	Imposter Name	Shed Form (Packed ULS)
B1	HEB200	8.5k
B2	HEB200	15.5k
B3	HEB200	11.5k

STEEL COLUMN SCHEDULE	
Type	Imposter Name
C1	HEB200X25
C2	HEB200X35
C3	HEB200X35


- 81 IS 15 DESIGN LOADS**
- THE APPLICABLE PROVINCIAL OR NATIONAL BUILDING CODE USED FOR THIS PROJECT IS - NATIONAL BUILDING CODE ALBERTA 2023 EDITION
  - ALL STRUCTURAL ELEMENTS ARE DESIGNED TO CONFORM TO THE SPECIFIED APPLICABLE PROVINCIAL OR NATIONAL BUILDING CODE
  - REFERENCE LOADS USED IN THE STRUCTURAL DESIGN ARE:  
GROUND SNOW LOAD:  
S<sub>g</sub> = 25.1 psf (1.2 kPa)  
S<sub>g</sub> = 2.1 psf (0.1 kPa)  
LATERAL LOADS:  
S<sub>l</sub> = 11.1 psf (0.5 kPa)  
IMPORTANCE CATEGORY LOW  
CONCENTRATED LOADS (UNLESS NOTED OTHERWISE):  
ROOFS = 200 lbs (1.9 kN)  
FLOORS = 2,000 lbs (9 kN)
  - BUILDING DESIGN LOADS USED ARE:  
a. PROPOSED SNOW LOAD: 30.2 psf (1.4 kPa)  
DESIGN DEAD LOAD (SELF-WEIGHT & SUPERIMPOSED): 12.0 psf (0.6 kPa)  
NET FACTORED WIND UPLIFT: 14.0 psf (0.7 kPa)  
b. ADDITIONAL LOADS DUE TO SNOW BUILD-UP ARE AS SHOWN ON THE ROOF FRAMING PLAN.  
c. SNOW LOAD BROWN IS FOR ULTIMATE LIMIT STATE (ULS) FOR SERVICEABILITY LIMIT STATE (SLS) MULTIPLY BY 0.30.  
d. ADDITIONAL LOADS DUE TO MECHANICAL EQUIPMENT SHALL BE INCLUDED. REFER TO MECHANICAL DRAWINGS FOR LOCATIONS AND WEIGHTS.  
e. SECOND FLOOR:  
DESIGN LIVE LOAD: 100.0 psf (4.8 kPa)  
DESIGN DEAD LOAD (SUPERIMPOSED): 8.0 psf (0.4 kPa)

**EAGLE BUILDERS**


1234 Main Street, Suite 100  
Calgary, Alberta T2C 1A1  
Phone: (403) 123-4567  
Email: info@eaglebuilders.ca

**PROFESSIONAL ENGINEER**  
Alberta  
No. 12345  
Exp. 12/31/2024


Help Farms, Sheep Barn  
Lethbridge County, Alberta




1 Girder Truss Elevation - Lamb Barn  
3/16" = 1'-0"




2 Girder Truss Elevation - Ewe Barn  
3/16" = 1'-0"




3 Girder Truss Elevation - Finishing Barn  
3/16" = 1'-0"




4 Truss Layout - Link  
3/16" = 1'-0"



5 Truss Elevation - Sorting Area  
3/16" = 1'-0"



6 Bolted Connection - 90degree  
1" = 1'-0"



7 Deck Angle Bolt Splice Detail  
1" = 1'-0"

CLIP ANGLE SCHEDULE	CLIP ANGLE SCHEDULE		FACTORED SHEAR RESISTANCE
	CLIP LENGTH	A OF BOLTS	
W8 (W10)	6"	2	71 kN
(W8) (W10)	(10)	2	108 kN
W12 (W14)	6"	3	107 kN
(W12) (W14)	(10)	3	162 kN
W16	12"	4	142 kN
(W16)	(12)	4	218 kN
W18	12"	5	178 kN
(W18)	(12)	5	276 kN
W21	12"	6	213 kN
(W21)	(12)	6	344 kN
W24	12"	7	244 kN
(W24)	(12)	7	393 kN
W27	12"	8	283 kN
(W27)	(12)	8	459 kN
W30	12"	9	318 kN
(W30)	(12)	9	518 kN
W36	12"	10	388 kN
(W36)	(12)	10	628 kN
W40	12"	11	428 kN
(W40)	(12)	11	698 kN

**EAGLE BUILDERS**

**gubal**

Mark Hogg, P.Eng. and John Hogg, P.Eng. are registered professional engineers in the Province of Alberta.





**PERMIT TO PRACTICE**  
Professional Engineer  
Alberta  
1000-10-01

**PROFESSIONAL ENGINEER**  
Alberta  
1000-10-01


Help Farms, Sheep Barn  
Lethbridge County, Alberta

3/16" = 1'-0"


3/16" = 1'-0"









1 Truss Ridge - Finishing  
12\"/>




15 Truss Tie-in - Finishing  
12\"/>




16 Beam at Ridge - Finish Barn  
12\"/>




2 Typical Gird Truss at Exterior Panel (4\"/>




3 IMP Support Exterior Panel - Roof Transition  
12\"/>




18 Beam Bearing Each Side of 5 1/2\"/>




19 Link Roof at Gutter (North)  
12\"/>




20 Link Roof at Gutter Brace (GL G)  
12\"/>




21 Link Roof at Gutter (South)  
12\"/>



22 Link Roof at Gutter Brace (South)  
12\"/>



23 Gutter Bearing GL 3  
12\"/>



24 Gutter Bearing GL 4  
12\"/>



15 February 2024

WSP File: CA0022671.6721 / BX30775

Hejo Farms Ltd.  
PO Box 491  
Coaldale, Alberta T1M 1N5

Attention: Johan Bennen



3102 – 12 Avenue South  
Lethbridge, Alberta T1H 5V1  
T: +1 403 327-7474  
www.wsp.com

**Re: Geotechnical Review and Evaluation  
NRCB Permitting of Proposed Manure Storage Lagoon  
SW-25-008-20-W4M, near Coaldale, Alberta**

As requested, WSP E&I Canada Limited (WSP) has carried out a geotechnical review and evaluation of the above-captioned site relative to the required protection of the groundwater resource, as required by the Agricultural Operation Practices Act, AB Reg. 267/2001 (hereinafter referred to as "AOPA"). This letter describes site soil conditions to support a permit application related to proposed liquid manure storage lagoon to be located in the northwest area of SW-25-008-20-W4M (refer to Figure 1, attached).

In order to demonstrate the suitability of the naturally existing soils for consideration as a naturally occurring protective layer to the groundwater, four boreholes were advanced at the site on January 2, 2024. The boreholes were advanced at the approximate locations denoted as JB1-24 to JB4-24 on Figure 1, attached.

The boreholes were advanced by a truck-mounted drill rig owned and operated by Chilako Drilling Services and extended to depths ranging between 11.6 m and 12.0 m below existing grades. The boreholes were logged by Larry Delong of Chilako Drilling Services.

In general, the natural mineral soils encountered within the boreholes consisted of a thin lacustrine silty clay layer which was underlain by clay till. While minor groundwater accumulation was noted during the drilling in JB2-24 at approximately 8.2 m depth, no groundwater resource (as defined by the AOPA) was identified within the 12 m investigation depth at the proposed lagoon site.

Samples of soil collected from the screened zone of boreholes JB1-24 to JB4-24 were subjected to laboratory grain size (i.e., hydrometer) analyses. The results (attached) indicate a textural breakdown of approximately:

**Table 1: Soil Textural Analyses**

Borehole/Depth	% Gravel	% Sand	% Silt	% Clay
JB1-24 / 9.0-10.5m	1	34	48	17
JB2-24 / 9.0-10.5m	1	35	46	18
JB3-24 / 9.0-10.5m	0	35	45	20
JB4-24 / 9.0-10.5m	0	30	52	18

To measure the *in situ* permeability of the subsurface soils, a 50 mm diameter PVC monitoring well was constructed in borehole JB1-24. The test well was screened from 7.7 m to 11.6 m depth. Well saturation of the 50 mm diameter monitoring well was carried out by filling the monitoring well to the top for

several consecutive days. After several days of testing, a three-hour water drop of 0.84 m was determined.

To calculate the permeability of the screened portion of the clay till strata at the test well location, a modified falling head test (as outlined in the USBR Engineering Geology Field Manual Volume 2 [2001]) was used. The input variables and output data are outlined on the attached In Situ Permeability Test report. The results of the permeability testing indicate an *in situ* hydraulic conductivity,  $k_s$ , of  $1.5 \times 10^{-7}$  cm/s at JB1-24.

Using the measured permeability of the clay stratum, the 3.9 m of clay screened at JB1-24 is estimated to represent the equivalent of approximately 26 m of naturally occurring materials having a hydraulic conductivity of  $1 \times 10^{-6}$  cm/s (the reference standard in AOPA). This represents natural material protection in excess of the minimum requirements outlined by the AOPA for liquid manure storage (minimum 10 m, Section 9.5-a).

### Conclusion

Based on the results of the current investigation, permeability testing, and our understanding of the site and proposed development at the site, it is WSP's opinion that the naturally occurring materials at the site satisfy the AOPA requirements for permitting the proposed liquid manure storage lagoon at this location.

We trust that this report satisfies your present requirements. Should you have any questions, please contact the undersigned at your convenience.

Yours truly,

WSP E&I Canada Limited



John Lobbezoo, P.Eng.  
Principal Geotechnical Engineer

Reviewed by:

Kevin Spencer, P.Eng., M.Eng.  
Sr. Associate, Geotechnical Engineer


<b>PERMIT TO PRACTICE</b>	
<b>WSP E&amp;I CANADA LIMITED</b>	
RM SIGNATURE: _____	_____
RM APEGA ID #: _____	10450
DATE: _____	15 Feb 2024
<b>PERMIT NUMBER: P004546</b>	
The Association of Professional Engineers and Geoscientists of Alberta (APEGA)	

### Attachments

- Figure 1 Borehole Locations
- In Situ Permeability Test Calculations
- Hydrometer Tests
- Soil Profile and Parent Material Description, Chilako Drilling Services



Figure 1  
BOREHOLE LOCATIONS  
PROPOSED LAGOON  
HEJO FARMS LTD.  
WSP File:BX30775  
February 2024



JB1-24

## In Situ Permeability Test

Modified Falling Head Permeability Equation

$$K_s = \frac{r^2}{2\ell\Delta t} \left[ \frac{\sinh^{-1} \frac{\ell}{r_e}}{2} \ln \left[ \frac{2H_1 - \ell}{2H_2 - \ell} \right] - \ln \left[ \frac{2H_1H_2 - \ell H_2}{2H_1H_2 - \ell H_1} \right] \right]$$

taken from USBR Engineering Geology Field Manual Volume 2 (2001)


JB1-24 - Hejo Farms

WSP File: BX30775

### INPUT VARIABLES


Terms	Value	Definition
D	0.0520	diameter of standpipe (m)
De	0.1500	diameter of borehole (m)
L	3.90	length of sand section (m)
h1	12.10	initial height of water above base of hole (m)
h2	11.26	final height of water above base of hole (m)
t	3.0	time of test (h)

$$k_s = 1.5E-07 \text{ cm/sec}$$



# HYDROMETER TEST

WSP Environment & Infrastructure Solutions



**Remarks:**

Summary				
D10 =	#N/A	mm	<b>Gravel</b>	1 %
D30 =	0.0098	mm	<b>Sand</b>	34 %
D60 =	0.0681	mm	<b>Silt</b>	48 %
Cu =	#N/A		<b>Clay</b>	17 %
Cc =	#N/A			


**Project No:** BX30775  
**Hole No:** JB1-24  
**Depth (m):** 9.0-10.5

**Client:** J. Bennan  
**Sample:** Sample # 3  
**Date:** February 8, 2024

**Tech:** CA

# HYDROMETER TEST

WSP Environment & Infrastructure Solutions




Remarks:	Summary				
	D10 =	#N/A	mm	Gravel	1 %
	D30 =	0.0099	mm	Sand	35 %
	D60 =	0.0677	mm	Silt	46 %
	Cu =	#N/A		Clay	18 %
	Cc =	#N/A			
<div>Project No: BX30775</div> <div>Hole No: JB2-24</div> <div>Depth (m): 9.5-10.5</div> <div>Client: J. Bennan</div> <div>Sample: Sample # 3</div> <div>Date: February 8, 2024</div> <div>Tech: CA</div>					



# HYDROMETER TEST

WSP Environment & Infrastructure Solutions




Remarks:	Summary				
	D10 =	#N/A	mm	Gravel	0 %
	D30 =	0.0070	mm	Sand	35 %
	D60 =	0.0676	mm	Silt	45 %
	Cu =	#N/A		Clay	20 %
	Cc =	#N/A			

Project No: BX30775	Client: J. Bennan	
Hole No: JB3-24	Sample: Sample # 1	
Depth (m): 9.0-10.5	Date: February 8, 2024	Tech: CA

# HYDROMETER TEST

WSP Environment & Infrastructure Solutions



Remarks:	Summary				
	D10 =	#N/A	mm	Gravel	0 %
	D30 =	0.0055	mm	Sand	30 %
	D60 =	0.0597	mm	Silt	52 %
	Cu =	#N/A		Clay	18 %
	Cc =	#N/A			

Project No: BX30775	Client: J. Bennan	
Hole No: JB4-24	Sample: Sample # 2	
Depth (m): 9.0-10.5	Date: February 8, 2024	Tech: CA

# CHILAKO DRILLING SERVICES LTD

Box 942 Coaldale, Alberta, T1M 1M8

(403) 345-3710

## SOIL PROFILE AND PARENT MATERIAL DESCRIPTION

Site Location: SW25-8-20W4, Hejo Farms (Johan Bennen)

Date: 2-Jan-24

Hole #	Location	Depth	Texture	Moisture	Geological	Sample	Remarks
JB1-24	0384841 5503531	0-0.15	CL	M	Topsoil		
		0.15-0.8	CL-SiCL	M	Lac		V. Firm, med plastic, brown
		0.8-6.4	CL	M	Till		Stiff, med plastic, brown
		6.4-7.6	CL	M	Till		Stiff, med plastic, brown, oxidized
		7.6		Sat			Sat sand streaks
		7.6-8.5	CL-C	M	Till		Stiff, med plastic, brown
		8.5-11.6	CL-C	M	Till	9.0-10.5	Stiff, med plastic, dark brown 50mm H.C. Well installed to 11.6m BGS Screen: 11.6-8.6m Sand: 11.6-7.7m Bentonite: 7.7-0.0m Stickup: 0.5m Hole Diameter: 0.15m
JB2-24	0384803 5503531	0-0.15	CL	M	Topsoil		
		0.15-0.7	CL-SiCL	M	Lac		V. Firm, med plastic, brown
		0.7-6.2	CL	M	Till		Stiff, med plastic, brown
		6.2-8.2	CL-C	M	Till		Stiff, med plastic, brown, oxidized
		8.2-9.3	CL	M	Till		Sat Sand lensing, water in test hole
		9.3-12.0	CL-C	M	Till	9.5-10.5	Stiff, med plastic, dark brown
JB3-24	0384803 5503561	0-0.15	CL	M	Topsoil		
		0.15-0.8	CL-SiCL	M	Lac		V. Firm, med plastic, brown
		0.8-4.0	CL	M	Till		V. Firm, med plastic, brown
		4.0-5.0	CL	M	Till		V. Firm, med plastic, yellow brown, some oxidation
		5.0-10.5	CL-C	M	Till	9.0-10.5	Stiff, med plastic, brown, some oxidation
		10.5-12.0	CL-C	M	Till		Stiff, med plastic, oxidized, VM sand streaks
JB4-24	0384843 5503561	0-0.15	CL	M	Topsoil		
		0.15-0.75	CL-SiCL	M	Lac		
		0.75-4.5	CL	M	Till		V. Firm, med plastic, brown
		4.5-6.2	CL	M	Till	4.0-4.5	V. Firm, med plastic, brown, M sand streaks
		6.2-8.1	CL	M	Till		Firm, med plastic, brown, sat sand streaks
		8.1-12.0	CL-C	M	Till	9.0-10.5	Stiff, med plastic, brown

Legend: L Loam  
C Clay  
S Sand  
Gr. Gravel  
Si Silt  
F Fine (sand)  
VF Very Fine (sand)

# NUCLEAR DENSITY FIELD TEST REPORT

 <small>3614 - 18th Avenue North Lethbridge, AB T1H 5S7</small>	CLIENT:	Dennis Dirtworx LTD.	ATTENTION: James Van Braak	REL JOB NO.: 242-450	 <small>1009 13th Avenue Coaldale, AB T1M 0E4</small>
	PROJECT:	Hejo Farms - Sheep Barn Pad	CONSULTANT:	JOB NO.: 24-251	
	LOCATION:	Hejo Farms - Rg Rd 201	ACTIVITY: Compaction - Subgrade	INSPECTOR: Z. Wittke	
REPORT NO.: #2	CONTRACTOR:	Dennis Dirtworx LTD.	SPECIFIED COMPACTION: 98.0 % Minimum	DATE: 2-Oct-2024	

TEST NO.	DATE TESTED	GRADE DEPTH (m)	TEST LOCATION	SOIL TYPE	PROBE DEPTH	DENSITY MODE	STANDARD PROCTOR (ASTM D698)		Material Percent Oversized	CONSTRUCTED			% PROCTOR DENSITY (ASTM 6938)	REMARKS
							DENSITY (kg/m <sup>3</sup> )	MOISTURE		DENSITY (kg/m <sup>3</sup> ) (Initial)	DENSITY (kg/m <sup>3</sup> ) (Corrected)	MOISTURE		
1	2/Oct/24	0.5m BG	50m E, 7m S of NW Corner of Pad	CLAY	300	NDT	1740	17.0%		1761		17.4%	101.2%	Retest of Shot #3, Report #1
2	2/Oct/24	0.5m BG	70m E, 5m S of NW Corner of Pad	CLAY	300	NDT	1740	17.0%		1717		16.7%	98.7%	Retest of Shot #4, Report #1
3	2/Oct/24	0.5m BG	90m E, 5m S of NW Corner of Pad	CLAY	300	NDT	1740	17.0%		1705		16.8%	98.0%	Retest of Shot #5, Report #1
4	2/Oct/24	@ Grade	20m S, 10m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%	5%	1774	1746	15.1%	100.3%	
5	2/Oct/24	@ Grade	20m S, 40m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%	5%	1777	1749	15.0%	100.5%	
6	2/Oct/24	@ Grade	20m S, 70m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%	10%	1813	1760	15.5%	101.2%	
7	2/Oct/24	@ Grade	20m S, 100m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%		1767		15.2%	101.6%	
8	2/Oct/24	@ Grade	20m S, 130m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%		1725		15.0%	99.1%	
9	2/Oct/24	@ Grade	20m S, 160m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%		1773		16.5%	101.9%	
10	2/Oct/24	@ Grade	20m S, 160m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%		1707		15.4%	98.1%	
11	2/Oct/24	@ Grade	20m S, 190m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%		1705		15.3%	98.0%	
12	2/Oct/24	@ Grade	30m S, 160m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%	10%	1814	1761	15.9%	101.2%	
13	2/Oct/24	@ Grade	30m S, 130m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%	5%	1787	1759	15.0%	101.1%	
14	2/Oct/24	@ Grade	30m S, 100m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%	5%	1799	1772	16.4%	101.8%	
15	2/Oct/24	@ Grade	30m S, 70m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%		1757		15.8%	101.0%	
16	2/Oct/24	@ Grade	50m S, 70m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%	10%	1799	1745	15.3%	100.3%	
17	2/Oct/24	@ Grade	50m S, 100m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%	10%	1792	1737	15.2%	99.8%	
18	2/Oct/24	@ Grade	50m S, 130m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%	15%	1833	1757	15.2%	101.0%	
19	2/Oct/24	@ Grade	50m S, 160m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%		1732		15.9%	99.5%	
20	2/Oct/24	@ Grade	70m S, 160m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%		1717		15.0%	98.7%	
21	2/Oct/24	@ Grade	70m S, 130m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%	5%	1776	1748	15.1%	100.4%	
22	2/Oct/24	@ Grade	70m S, 100m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%	20%	1863	1768	16.3%	101.6%	
23	2/Oct/24	@ Grade	70m S, 70m W of NE Corner of Pad	CLAY	300	NDT	1740	17.0%		1716		18.3%	98.6%	
24														
25														
26														
AVERAGE				CLAY						Moisture %		15.8%	Compaction %	100.2%

<div>Additional Comments:</div> <div>Fill Material Consisting of Clay Sheeps Foot Packer Used</div>	<div>Distribution List:</div> <div>1. James Van Braak - <a href="mailto:jamesvb@dennisdirtworx.ca">jamesvb@dennisdirtworx.ca</a></div>	<div>Authorized Signatures:</div> <div><div><div></div><div>Materials Technician: Zayne Wittke</div></div><div><div></div><div>Reviewed By: Devon Rowley</div></div></div>		<div>Contractor's Representative</div>
		<div>Project Manager</div> <div>Page 24 of 25</div>		



