



In consideration of Decision Summary LA25043, Authorization LA25043 is issued to:

Name: 1717868 Ab Inc. operating as Anchor J Ranches (the “permit holder”)
Address: RR #1, Hanna AB T0J 1P0
Contact person: Greg Johnson

Permitted construction (based on the submitted site plan):

- Catch basin – irregular dimension final dimensions: 37,376 m³

The permit holder shall comply with the requirements of the *Agricultural Operation Practices Act* (AOPA) and the regulations passed pursuant to that Act.

The permit holder shall adhere to the descriptions, the site plan, building plans, engineering reports and other attached documents included with filed Application LA25043.

The permit holder shall contact the NRCB at least 10 working days in advance of the desired inspection date to schedule the inspection in condition #4.

The permit holder is responsible for all costs associated with sampling, testing, recording, and reporting requirements (this includes post construction reports).

Construction conditions

Catch basin

1. Construction completion report

The permit holder shall provide the NRCB with a written construction completion report for the catch basin. The report shall be stamped and signed by a “professional engineer,” as defined in the Standards and Administration Regulation, and shall:

- Confirm the final size of the catch basin, including the depth below grade;
- Certify that the liner material used in the catch basin is the same material that was submitted for hydraulic conductivity testing;
- Confirm that the liner is 1 m thick
- Provide the in-situ density test results of the constructed catch basin liner.

2. Water table

The permit holder shall cease construction and notify the NRCB immediately if the water table is encountered within 1 m of the construction zone of the compacted clay liner.

3. Construction completion deadline

The permit holder shall complete construction of the catch basin prior to December 31, 2026. Upon request, this deadline may be extended by the NRCB in writing.



4. Post construction inspection

The permit holder shall not allow manure contaminated runoff to enter the catch basin until NRCB personnel have inspected the facility and confirmed, in writing, that it has been constructed in accordance with the terms and conditions of this permit.

This authorization becomes effective immediately. The authorization conditions will remain in effect unless amended in writing by the NRCB and must read in conjunction with Anchor J.'s deemed permit.

September 22, 2025

(original signed)
Carina Weisbach
Approval Officer